

# Contents

List of Figures .....	vii
List of Tables .....	viii
Introduction .....	1
<b>Versatile Solutions</b> .....	<b>2</b>
Benefits of Concrete Overlays .....	2
Two Concrete Overlay Systems .....	2
Bonded Overlay Systems .....	2
Unbonded Overlay Systems .....	2
Maintenance and Rehabilitation Solutions .....	3
Pavement Preservation .....	3
Routine Maintenance .....	3
Preventive Maintenance .....	3
Minor Rehabilitation .....	3
Major Rehabilitation .....	3
<b>Uses and Key Elements of Each Concrete Overlay Type</b> .....	<b>4</b>
Bonded Concrete Overlay System .....	4
Unbonded Concrete Overlay System .....	5
<b>Evaluating Existing Pavement Conditions</b> .....	<b>6</b>
Historical Data and Future Projections .....	6
Visual Examination .....	6
Pavement Coring .....	6
Optional Analyses .....	6
Material-Related Distress .....	7
Distress Surveys .....	7
Drainage Surveys .....	7
Roughness and Surface Friction Tests .....	7
Elevations and Grade Restrictions .....	7
Condition Assessment Profile .....	7
Condition Evaluation Report .....	7
Summary of Pavement Evaluation Process .....	9
<b>Selecting Appropriate Concrete Overlay Solution</b> .....	<b>10</b>
<b>Bonded Overlay Systems (2-page overviews)</b>	
<b>Bonded Concrete Overlays of Concrete Pavements</b> .....	<b>12</b>
Uses .....	12
Performance .....	12
Overlay Process .....	12
Step 1. Pavement Evaluation .....	12
Step 2. Overlay Design .....	12
Step 3. Preoverlay Work .....	13
Step 4. Construction .....	13
Future Repairs .....	13
<b>Bonded Concrete Overlays of Asphalt Pavements</b> .....	<b>14</b>
Uses .....	14
Performance .....	14
Overlay Process .....	14
Step 1. Pavement Evaluation .....	14
Step 2. Overlay Design .....	14
Step 3. Preoverlay Work .....	15
Step 4. Construction .....	15
Future Repairs .....	15
<b>Bonded Concrete Overlays of Composite Pavements</b> .....	<b>16</b>
Uses .....	16
Performance .....	16
Overlay Process .....	16
Step 1. Pavement Evaluation .....	16
Step 2. Overlay Design .....	16
Step 3. Preoverlay Work .....	17
Step 4. Construction .....	17
Future Repairs .....	17
<b>Unbonded Overlay Systems (2-page overviews)</b>	
<b>Unbonded Concrete Overlays of Concrete Pavements</b> .....	<b>18</b>
Uses .....	18
Performance .....	18
Overlay Process .....	18
Step 1. Pavement Evaluation .....	18
Step 2. Overlay Design .....	18
Step 3. Preoverlay Work .....	19
Step 4. Construction .....	19
Future Repairs .....	19
<b>Unbonded Concrete Overlays of Asphalt Pavements</b> .....	<b>20</b>
Uses .....	20
Performance .....	20
Overlay Process .....	20
Step 1. Pavement Evaluation .....	20
Step 2. Overlay Design .....	20
Step 3. Preoverlay Work .....	21
Step 4. Construction .....	21
Future Repairs .....	21
<b>Unbonded Concrete Overlays of Composite Pavements</b> .....	<b>22</b>
Uses .....	22
Performance .....	22
Overlay Process .....	22
Step 1. Pavement Evaluation .....	22
Step 2. Overlay Design .....	22
Step 3. Preoverlay Work .....	23
Step 4. Construction .....	23
Future Repairs .....	23
<b>Design of Concrete Overlays</b> .....	<b>24</b>
Design Objectives .....	24
Bonded Overlay Systems .....	24
Unbonded Overlay Systems .....	24
Overlay System Design Inputs .....	24
Existing Pavement Characterization .....	24
Surface Considerations .....	24
Structural Considerations .....	24
Traffic Characterization .....	25
Material Properties .....	25
Climatic Factors .....	25
Constraints .....	25
Distress Mode .....	26
Design Selection .....	26
Design of Bonded Overlay Systems .....	28
Bonded Overlays of Concrete Pavements .....	28
Bonded Overlays of Asphalt Pavements .....	28
Bonded Overlays of Composite Pavements .....	29

Design of Unbonded Overlay Systems .....	29	Early Opening of Overlays to Traffic .....	54
Unbonded Overlays of Concrete Pavements .....	29	Quality of Bond for Bonded Overlays of Existing	
Unbonded Overlays of Asphalt Pavements .....	30	Concrete Surfaces .....	54
Unbonded Overlays of Composite Pavements .....	30	Strength Conversions for Opening to Traffic .....	56
Widening and Lane Addition Design .....	30	Conversions .....	56
<b>Miscellaneous Design Details .....</b>	<b>31</b>	Strength Criteria for Opening Bonded Systems to Traffic .....	56
Curbs and Gutters .....	31	Existing Concrete Pavement .....	56
Manhole .....	31	Existing Asphalt Pavements .....	56
Transitions .....	31	Strength Criteria for Opening Unbonded Systems	
Mill and Fill Transitions for Bonded Concrete Overlays .....	31	to Traffic .....	56
New Transitions for Bonded Concrete Overlays .....	32	Minimizing Early Loading Fatigue Damage .....	56
New Transitions for Unbonded Concrete Overlays .....	32		
Transition Details for Bonded Concrete Overlays .....	33	<b>Considerations for Developing Project and Supplemental</b>	
Transition Details for Unbonded Concrete Overlays .....	33	<b>Specifications .....</b>	<b>64</b>
Lane Addition .....	33	General .....	64
<b>Concrete Overlay Materials .....</b>	<b>34</b>	Contractor Submittal Considerations .....	64
Type of Mixture .....	34	Scheduling and Conflicts .....	64
Conventional Mixtures .....	34	Limitations of Operations .....	64
Expedited Mixtures .....	34	Method of Measurement and Basis of Payment .....	64
Concrete Materials .....	34	Materials .....	64
Cementitious Materials .....	34	Separation Layer for Unbonded Overlays .....	64
Aggregates .....	34	Construction .....	64
Water-Cementitious Materials Ratio .....	34	Preoverlay Repairs .....	64
Admixtures .....	34	Bonded Overlays Over Concrete .....	65
Fiber-Reinforced Concrete .....	35	Bonded Overlays Over Asphalt .....	65
Synthetic Fibers (Macro and Micro) .....	35	Unbonded Overlays Over Concrete .....	65
Steel Fibers .....	35	Unbonded Overlays Over Asphalt .....	65
Blended Fibers .....	35	Surface Cleaning .....	65
Separation Layer Materials .....	35	Bonded Concrete Overlays Over Concrete	
Incidental Materials .....	36	or Asphalt .....	65
<b>Managing Concrete Overlay Work Zones under Traffic .....</b>	<b>37</b>	Unbonded Concrete Overlays Over Concrete	
Objectives of Work Zone Management .....	37	or Asphalt .....	65
Safety .....	37	Concrete Placement .....	65
Traffic Flow .....	38	Grade Control .....	65
Cost-Effectiveness .....	38	Overlay Placement .....	65
Pavement Performance .....	38	Liquid Membrane Curing .....	65
Work Zone Space Considerations .....	38	Joint Sawing .....	65
Paving Equipment Clearances .....	38	General .....	65
Reducing Clearance with Paver Modifications .....	38	Joint Width .....	66
Reducing Clearance with Alternative Control Options .....	39	Joint Seal .....	66
Other Clearances .....	39	Timing .....	66
Construction Traffic Control .....	39	Bonded Overlays Over Concrete .....	66
Concrete Overlay Staging .....	39	Bonded Overlays Over Asphalt .....	66
Two-Lane Highway under Traffic .....	39	Unbonded Overlays .....	66
Filllets .....	40	<b>Repairs of Concrete Overlays .....</b>	<b>67</b>
Continuous Production .....	40	Repairs of Bonded or Thin Unbonded Concrete Overlays .....	67
Two-Lane Highway Expanded to Three Lanes		Repairs of Full-Depth Unbonded Concrete Overlays .....	68
Under Traffic .....	40	<b>Appendix A. Evaluation and Selection Tables .....</b>	<b>69</b>
Four-Lane Divided Highway without Crossovers and		<b>Appendix B. Sample Geotextile Specifications (Germany) .....</b>	<b>70</b>
under Traffic .....	41	<b>Appendix C. Innovative Methods for Accelerated Concrete</b>	
<b>Key Points for Concrete Overlay Construction.....</b>	<b>52</b>	<b>Overlay Construction .....</b>	<b>71</b>
<b>Accelerated Construction .....</b>	<b>54</b>	<b>Sources .....</b>	<b>74</b>
Approach and Considerations .....	54	References .....	74
		Bibliography .....	75